

**TABELA ROBÓT ZIEMNYCH - PRZEBUDOWA DROGI LEŚNEJ NR 1108 W ODDZIALE NR 81, 82, 85, 86
LEŚNICTWA KAMIENICA WRAZ PRZEBUDOWĄ SZLAKU ZRYWKOWEGO NR S1124 W ODDZIALE NR 86,
87 LEŚNICTWA KAMIENICA.**

Kilometraż	Powierzchnia [m ²]		Powierzchnia średnia [m ²]		Odległości [m]	Objętości [m ³]		Suma [m ³]	
	W	N	W	N		W	N	+	-
0+000.00	0.54	0.31						-	-
0+020.00	11.45	0.26	6.00	0.29	20.00	119.90	5.70	114.20	-
0+040.00	22.40	0.00	16.93	0.13	20.00	338.50	2.60	450.10	-
0+060.00	22.00	0.00	22.20	0.00	20.00	444.00	-	894.10	-
0+080.00	16.60	0.00	19.30	0.00	20.00	386.00	-	1 280.10	-
0+100.00	3.68	5.67	10.14	2.84	20.00	202.80	56.70	1 426.20	-
0+120.00	4.22	3.78	3.95	4.73	20.00	79.00	94.50	1 410.70	-
0+140.00	11.20	0.24	7.71	2.01	20.00	154.20	40.20	1 524.70	-
0+160.00	7.99	0.73	9.60	0.49	20.00	191.90	9.70	1 706.90	-
0+180.00	5.42	1.75	6.71	1.24	20.00	134.10	24.80	1 816.20	-
0+200.00	8.49	0.87	6.96	1.31	20.00	139.10	26.20	1 929.10	-
0+220.00	10.37	0.65	9.43	0.76	20.00	188.60	15.20	2 102.50	-
0+240.00	15.55	3.08	12.96	1.87	20.00	259.20	37.30	2 324.40	-
0+260.00	16.10	2.50	15.83	2.79	20.00	316.50	55.80	2 585.10	-
0+280.00	4.71	3.03	10.41	2.77	20.00	208.10	55.30	2 737.90	-
0+300.00	3.15	4.46	3.93	3.75	20.00	78.60	74.90	2 741.60	-
0+320.00	3.02	4.19	3.09	4.33	20.00	61.70	86.50	2 716.80	-
0+340.00	1.33	6.93	2.18	5.56	20.00	43.50	111.20	2 649.10	-
0+360.00	0.74	7.61	1.04	7.27	20.00	20.70	145.40	2 524.40	-
0+380.00	0.60	7.62	0.67	7.62	20.00	13.40	152.30	2 385.50	-
0+400.00	1.95	3.45	1.28	5.54	20.00	25.50	110.70	2 300.30	-
0+420.00	2.27	2.84	2.11	3.15	20.00	42.20	62.90	2 279.60	-
0+440.00	3.80	1.62	3.04	2.23	20.00	60.70	44.60	2 295.70	-
0+460.00	4.73	1.02	4.27	1.32	20.00	85.30	26.40	2 354.60	-
0+480.00	1.86	4.47	3.30	2.75	20.00	65.90	54.90	2 365.60	-
0+500.00	1.76	5.62	1.81	5.05	20.00	36.20	100.90	2 300.90	-
0+520.00	1.71	6.76	1.74	6.19	20.00	34.70	123.80	2 211.80	-
0+540.00	2.56	5.78	2.14	6.27	20.00	42.70	125.40	2 129.10	-
0+560.00	12.46	0.11	7.51	2.95	20.00	150.20	58.90	2 220.40	-
0+580.00	22.00	0.00	17.23	0.06	20.00	344.60	1.10	2 563.90	-
0+600.00	0.70	70.80	11.35	35.40	20.00	227.00	708.00	2 082.90	-
0+613.00	0.00	75.00	0.35	72.90	13.00	4.55	947.70	1 139.75	-
Razem:						4 499.35	3 359.60		

**TABELA ROBÓT ZIEMNYCH - PRZEBUDOWA DROGI LEŚNEJ NR 1108 W ODDZIALE NR 81, 82, 85, 86
LEŚNICTWA KAMIENICA WRAZ PRZEBUDOWĄ SZLAKU ZRYWKOWEGO NR S1124 W ODDZIALE NR 86,
87 LEŚNICTWA KAMIENICA.**

Kilometraż	Powierzchnia [m ²]		Powierzchnia średnia [m ²]		Odległości [m]	Objętości [m ³]		Suma [m ³]	
	W	N	W	N		W	N	+	-
0+613.00	0.00	75.00						-	-
0+620.00	0.00	95.36	0.00	85.18	7.00	-	596.26	-	596.26
0+640.00	0.00	87.15	0.00	91.26	20.00	-	1 825.10	-	2 421.36
0+660.00	0.18	2.70	0.09	44.93	20.00	1.80	898.50	-	3 318.06
0+680.00	1.37	5.49	0.78	4.10	20.00	15.50	81.90	-	3 384.46
0+700.00	1.64	7.18	1.51	6.34	20.00	30.10	126.70	-	3 481.06
0+720.00	3.51	4.10	2.58	5.64	20.00	51.50	112.80	-	3 542.36
0+740.00	6.78	1.66	5.15	2.88	20.00	102.90	57.60	-	3 497.06
0+760.00	8.07	0.83	7.43	1.25	20.00	148.50	24.90	-	3 373.46
0+780.00	11.02	0.89	9.55	0.86	20.00	190.90	17.20	-	3 199.76
0+800.00	11.91	1.00	11.47	0.95	20.00	229.30	18.90	-	2 989.36
0+820.00	6.66	6.44	9.29	3.72	20.00	185.70	74.40	-	2 878.06
0+840.00	4.25	1.61	5.46	4.03	20.00	109.10	80.50	-	2 849.46
0+860.00	10.55	0.00	7.40	0.81	20.00	148.00	16.10	-	2 717.56
0+880.00	16.25	0.00	13.40	0.00	20.00	268.00	-	-	2 449.56
0+900.00	6.40	2.05	11.33	1.03	20.00	226.50	20.50	-	2 243.56
0+920.00	4.02	3.50	5.21	2.78	20.00	104.20	55.50	-	2 194.86
0+940.00	0.02	13.65	2.02	8.58	20.00	40.40	171.50	-	2 325.96
0+960.00	0.00	16.35	0.01	15.00	20.00	0.20	300.00	-	2 625.76
0+980.00	0.00	10.26	0.00	13.31	20.00	-	266.10	-	2 891.86
1+000.00	0.00	9.15	0.00	9.71	20.00	-	194.10	-	3 085.96
1+020.00	1.48	0.02	0.74	4.59	20.00	14.80	91.70	-	3 162.86
1+040.00	9.05	0.00	5.27	0.01	20.00	105.30	0.20	-	3 057.76
1+060.00	13.80	0.00	11.43	0.00	20.00	228.50	-	-	2 829.26
1+080.00	17.05	0.00	15.43	0.00	20.00	308.50	-	-	2 520.76
1+100.00	0.00	4.70	8.53	2.35	20.00	170.50	47.00	-	2 397.26
1+120.00	0.00	3.82	0.00	4.26	20.00	-	85.20	-	2 482.46
1+140.00	1.33	0.34	0.67	2.08	20.00	13.30	41.60	-	2 510.76
1+160.00	1.65	0.00	1.49	0.17	20.00	29.80	3.40	-	2 484.36
1+180.00	1.27	0.15	1.46	0.08	20.00	29.20	1.50	-	2 456.66
1+200.00	0.00	7.40	0.64	3.78	20.00	12.70	75.50	-	2 519.46
1+220.00	5.80	0.04	2.90	3.72	20.00	58.00	74.40	-	2 535.86
1+240.00	8.05	0.00	6.93	0.02	20.00	138.50	0.40	-	2 397.76
1+260.00	7.40	0.00	7.73	0.00	20.00	154.50	-	-	2 243.26
1+280.00	1.50	0.00	4.45	0.00	20.00	89.00	-	-	2 154.26
1+300.00	0.00	6.30	0.75	3.15	20.00	15.00	63.00	-	2 202.26
1+320.00	0.05	1.88	0.03	4.09	20.00	0.50	81.80	-	2 283.56
1+340.00	0.52	0.21	0.29	1.05	20.00	5.70	20.90	-	2 298.76
			0 26	0 75	20 00	5 20	14 90		

1+360.00	0.00	1.28	0.20	0.10	20.00	0.20	17.00	-	2 308.46
1+380.00	0.05	1.59	0.03	1.44	20.00	0.50	28.70	-	2 336.66
1+400.00	0.00	1.52	0.03	1.56	20.00	0.50	31.10	-	2 367.26
1+420.00	0.38	0.87	0.19	1.20	20.00	3.80	23.90	-	2 387.36
1+440.00	0.70	0.00	0.54	0.44	20.00	10.80	8.70	-	2 385.26
1+460.00	0.50	0.63	0.60	0.32	20.00	12.00	6.30	-	2 379.56
1+480.00	4.50	0.00	2.50	0.32	20.00	50.00	6.30	-	2 335.86
1+500.00	0.85	4.51	2.68	2.26	20.00	53.50	45.10	-	2 327.46
1+520.00	0.07	4.55	0.46	4.53	20.00	9.20	90.60	-	2 408.86
1+540.00	0.00	3.80	0.04	4.18	20.00	0.70	83.50	-	2 491.66
1+560.00	0.54	0.37	0.27	2.09	20.00	5.40	41.70	-	2 527.96
1+580.00	0.73	0.17	0.64	0.27	20.00	12.70	5.40	-	2 520.66
1+600.00	2.46	0.00	1.60	0.09	20.00	31.90	1.70	-	2 490.46
			Razem:		3 422.60	5 913.06			